

**BANK NOTE PAPER MILL INDIA PRIVATE LIMITED,
CIN: U21090KA2010PTC055475
CORPORATE OFFICE, MYSORE**

ENQUIRY No: BNPM/ENQ/Civil work for crèche/471/2017-18

Date: 23.03.2018

Last date of Submission of quotation: 29.03.2018 at 1500 hrs

1. Scope of work:

Civil Miscellaneous work for crèche facility.

2. Terms & Conditions:

S. No.	Particulars	Quantity
1.	Payment Terms	100% of the bill value shall be paid on completion of works at BNPM Premises and on production of all required documents by the supplier after certification of engineer in charge.
2.	Price	Price should be inclusive of all taxes & duties.
3.	Freight	Shall be included in quoted price
4.	Packing & Forwarding	Shall be included in quoted price
5.	Delivery Terms	It is responsible of the bidder to arrange transportation and labour required for completion of works on FOR destination basis.
6.	Delivery Period	20 days
7.	Material to be delivered at	Plant Maintenance Civil Bank Note Paper Mill India Private Limited Note Mudran Nagar Mysore 570 003
8.	Contact person in Civil department	Mr. Raghavendra S A 0821 2401 191 Mr. M. Karthikeyan 0821 2401 189



3. Price Bid Format :

SL. NO.	Reference of BOQ ITEM KPWD/CPWD	Description of works	Unit	Qty	Unit Rate	Tax / Duty	Freight, P&F Charges	Unit rate including all taxes & duties	Grand total inclusive of all taxes and duties (DAP, BNPM, Mysore)
1	15.52.1	KSRB 15-15.3 : Providing and applying painting in one coat with plastic emulsion paint of approved brand and manufacture on wall surface to give an even approved shade after thoroughly brushing the surface, free from mortar drops and other foreign matter including preparing the surface even and sand paper smooth, cost of materials, labour, complete as per specifications.	Sqm	200.00					
2	6.24	KSRB 6-7.2 : Construction of partition wall 11.2 cms thick with non modular ground moulded burnt bricks of class designation 5.0 Newton per sqmm with cement mortar 1:4 including providing and fixing plaster mesh manufactured out of hot dipped galvanised iron of nominal thickness 0.35 mm. 100 mm. wide as per I.S. 2212/1991 at 7.5 m. c to c including cost of materials, labour charges, scaffolding, curing complete as per specifications. Specification No. KBS 6.2	Sqm	3.00					



3	9.80	KSRB 9-27.1 : Fixing of door frame in an existing opening including embedding frame in floor and walls after cutting masonry for holdfasts for embedding holdfast in cement concrete 1:3:6 of 20mm and down size granite metal painting two coats of coal tar to sides of frame, making good the damages to walls and floor as required and disposal of the debries with lead upto 50 m. including cost of materials, labour charges, complete as per specifications. (P.No. 57, I.No. 9.80 of PWD SR 2016-17)	Nos	1.00					
4	14.52	Providing and laying plat form using prepolished, water cut / gang saw 40mm thick telephonic Black Granite. laid on existing vertical -supports and fixing in CM 1:3 proportion. Including cutting to required shape, pattern with paper joints, including full rounding for nosing, finished with cement mortar, pointed with colour pigments to match the colour of slab making through jointing with sealant, making holes 25mm x 12mm grooves in joints including curing. (P.No. 108, I.No. 14.52 of PWD SR 2015-16)	Sqm	5.00					
5	14.38	KSRB 14-16.1 : Providing skirting upto 30 cms. height with cement mortar 1:3 finished with a floating coat of neat cement including rounding off junctions floor, overall 15 mm thick including cost of materials, labour, complete as per specifications. Specification No.KBS 14.5	Sqm	10.00					
6	14.56	Providing half nosing for 20mm thick granite slab using required machinery including cost and conveyance of all materials, labour for all items of work, HOM of equipment etc., complete as per specification	m	20.00					



7	13.85.2	Providing and fixing Chlorinated Poly Vinyl Chloride (CPVC) pipes conforming to IS 15778, having thermal stability for hot and cold water supply including all CPVC plain and brass threaded fittings including fixing the pipe with clamp at 1.00 mtr spacing. This includes jointing of pipes and fittings with one step CPVC solvent cement and testing of joints complete. (internal work exposed on wall) - 20mm nominal OD pipes	m	25.00					
8	13.85.5	Providing and fixing Chlorinated Poly Vinyl Chloride (CPVC) pipes conforming to IS 15778, having thermal stability for hot and cold water supply including all CPVC plain and brass threaded fittings including fixing the pipe with clamp at 1.00 mtr spacing. This includes jointing of pipes and fittings with one step CPVC solvent cement and testing of joints complete. (internal work exposed on wall) - 40mm nominal OD pipes	m	10.00					
9	12.113.2	Providing and fixing CI Nahani trap of approved make conforming to ISI specifications and construction of Cistern in M-15 as per directions (Rate is inclusive of cost of materials and fixtures and conveyance of materials to work spot). - 12.5cms x 7.5cms	Each	2.00					
10	13.23	KSRB13-6.1-1 : Providing and fixing in position brass bib cock of approved quality 15mm nominal bore including cost of all materials, labour and HOM of equipments with all leads complete as per specifications. Specification No.KBS 13.2.2 / 13.3	Each	1.00					



11	13.26	KSRB13-6.2-1 : Providing and fixing in position brass stop cock of approved quality 15mm nominal bore including cost of all materials, labour and HOM of equipments with all leads complete as per specifications. Specification No.KBS 13.2.2 / 13.3	Each	1.00					
12	1073	HOM cutting and grinding machine	Days	2.00					
13	16.31	KSRB 24-36 : Removing the glazed tiles in patches in area exceeding 10 tiles and not exceeding 5 sqm including removing old tiles preparing surfaces and laying or setting new or old tiles complete including cost of materials, (excluding cost of tiles) labour, complete as per specifications. Specification No.KBS	Sqm	5.00					
14	12.111	Providing and fixing 7.5 cms to 15.00 cms dia NP grating 100 mm dia. (P.No. 88, I.No. 12.111 of PWD SR 2015-16)	Each	5.00					
15	4.29.2	KSRB 4-6.2 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for suspended floors, landings, balconies and likes, thickness upto 200 mm including cost of all materials, labour complete as per specifications for heights more than 3.50m from ground level. - 0 to 5 mtrs. Specification No. KBS 4.6.2	Sqm	5.00					



16	13.90	Providing and fixing polished granite sink of size 60cms x 60cms of 23cm thick, the sink portion shall be 15cm in depth of shapes oval / round / square over brick masonry in cement mortar 1:6 including cost and conveyance of all materials, labour for all items of work, HOM of equipment with all lead and lift, loading and unloading, transportation charges and all other incidental charges etc., complete as per specification and directions of the Engineer-in-charge of the work.	Each	1.00					
17	12.116.1	Providing and fixing to wall, ceiling and floor unplasticised PVC 6.00 kgs/sqcm working pressure with pipe fittings, wall clips etc., and making good the wall, ceiling and floor for sanitary pipelines including cost of all materials, labour charges, HOM of acquirements and testing complete as per specifications. - 110mm dia	m	25.00					
				Grand Total					
				Grand Total In words					

We hereby confirm that

1. We accept all terms & conditions mentioned in the enquiry.
2. Price quoted is inclusive of GST, duties, P&F, freight etc. on DAP, BNPM, Mysore basis.

Signature of bidder:.....

Name of the Firm:.....



Seal of the firm:

